



Ministry of Health & Social Services

Health Headquarters

P. O Box 24

Brades

Montserrat. W. I.

Tel: (664) 491-2552/2880

Fax: (664) 491-3131

Email: mehcs@gov.ms

MECHS/4/13/7

March 2nd, 2017


Dear Sir/Madam,

ADDENDUM No. 1 – Update to Bill of Quantities

Re: Tender for Construction of Worker's Building – New Windward

Tenderers are asked to note there has been an update to the Bill of Quantities for the Above mentioned project. All queries and clarification relating to this tender should be sent to Candita Greenaway, Assistant Secretary MoHSS at greenawayc@gov.ms.

Best Regards


.....
Elijah K Silcott
Chairperson
MoHSS Departmental Tender Committee

EKS/cg

New Windward Worker's Building Bill of Quantities					
Item	Description	Units	Qty	Rate	Total
1.00	Preliminaries				
	Contractor's Preliminaries, Mobilisation. and Employees' Insurance.	Item			
	Contractor shall be responsible for ensuring a safe working environment and proper protection of the works during construction.				
2.00	Earthworks and blinding preparation				
2.01	Excavate for building foundation; column and foundation footing.	m ³	35.00		
2.02	2" concrete blinding in preparation for foundation reinforcement.	m ²	32.00		
3.00	In-situ concrete works				
3.01	Supply, place and compact 3000 psi in-situ concrete to building foundation.	m ³	5.50		
3.02	Supply, place and compact 3000 psi in-situ concrete to structural columns, beams, on-grade slab and roof slab. Concrete shall be be compacted using poker vibrator.	m ³	13.25		
4.00	Reinforcement works				
4.01	No. 66 brc. fabric to on-grade slab.	m ²	15.45		
4.02	Steel reinforcement				
	1/2" bar	kg	168.79		
	3/8" bar	kg	300.95		
	5/8" bar	kg	250.00		
5.00	Hollow Block Works				
5.01	Concrete hollow blocks reinforce with 1/2" bar every other core and concrete filled.	m ²	54.68		
5.02	1/2" Render to hollow block works: Internal and external surface area.	m ²	90.00		
6.00	Windows and Doors				
6.01	Jalousie aluminium 36"x48" window	nr.	1		
6.02	Jalousie aluminium 30"x30" window	nr.	2		
6.03	Jalousie aluminium 36"x36" window	nr.	1		
6.04	Aluminium door with aluminium louvre inserts; 36"x80"	nr.	1		
6.05	H/C flush door; 30"x80"	nr.	1		
7.00	Plumbing				
7.01	Supply and install wash hand basin and other associated components to complete this task: pipe tap, water line etc.	nr.	1		
7.02	Waste water drain pipe connection for septic tank and wash hand basin.	nr.	1		
7.03	Supply and install complete set of flush toilet.	nr.	1		
7.04	Supply material and labour for construction of shower facilities inclusive installation of all fixtures.				

8.00	Formwork				
8.01	Supply all necessary formwork needed for the construction of the building. This includes all areas of the substructure and the superstructure.	Item			
9.00	Septic Tank				
9.01	In accordance with Sheet No.5, Supply Material, Labour and Equipment for the construction of Septic Tank. Include for construction of reinforced concrete slab that is reinforced with ½" bars. Concrete hollow blocks reinforced with 1/2" bar at every other core for septic and soakpit. Include for construction of reinforced concrete access covers and plug. Render internal surface of hollow concrete block. Include for all the necessary formwork. Supply, fill and pack small and medium size igneous type boulders to soakpit.	Item			
10.00	Electrical fittings and fixtures				
10.01	Supply and place single pole switch 48" A.F.F.	nr.	3		
10.02	Supply and place 110 outlets 18" A.F.F.	nr.	1		
10.03	Supply and place wall mounted fixture.	nr.	3		
10.04	Supply and place weather protected fixture.	nr.	1		
10.05	Supply and install 2' wall mounted flourescent fixture.	nr.	1		
10.06	Supply and install 1 KVA Transformer.	nr.	1		
10.07	Supply and install 220 V Distribution panel.	nr.	1		
10.08	Supply and install 110 V Distribution panel.	nr.	1		
10.09	Supply and install earthing - 6' x 1/2 diameter copper rod	item			
10.10	Provide for Monlec meter and fuse installation.	item			
10.11	Supply and install 1.5 mm gauge electrical cable for lighting fixtures.	item			
10.12	Supply and install 2.5 mm gauge electrical cable for switch fixtures.	item			
Total					