



**MINISTRY OF COMMUNICATIONS, WORKS & LABOUR**

**P O BOX 311, BRIDES, MONTSERRAT, W I**

**◆ Tel (066) 491-2521/2522 ◆ Fax (066) 491-0639 ◆ E-mail [mcwl@stx.mt](mailto:mcwl@stx.mt)**

December 17<sup>th</sup>, 2014

Dear Sir/Madam,

**Re: Tender for Repainting of Airport Terminal Building (Labour Only)**

Please note below the addendum to the Scope of Works, for the Labour Only Tender for the Painting of the Airport Terminal Building under the Airport Maintenance project, issued on the December 9<sup>th</sup> 2014.

As a result of the amendments made to the Scope of Works, for Tender for Repainting of Airport Terminal Building (Labour Only) has been further extended from **Friday 19<sup>th</sup> December 2014 to Tuesday 23<sup>rd</sup> December 2014, 3:00pm.**

Best Regards

*for Williams*

Beverly Mendes  
The Chairperson  
Departmental Tender Committee  
Ministry of Communications, Works & Labour

BEM/GF

# Airport Terminal Building Repainting

## Scope of Works

Note: The successful contractor is required to supply all labour to complete the works described, unless where indicated.

Item	Description	Qty.	Unit	Rate	Price
<b>1</b>	<b>External Block Wall Surface</b>				
1.1	Clean dust and mildew from all external block wall surfaces.	1	sum.		
1.2	Apply sealant to key areas on all external block wall surfaces (as advised by Project Architect)	1	sum.		
1.3	Apply 2# coats of 'Weather Barrier', semi-gloss, water-based paint on prepared surface (colour to be specified by Project Architect).	7,175	sq ft		
<b>2</b>	<b>External Railings</b>				
2.1	Apply 2# coats of 'Weather Barrier', semi-gloss, water-based paint on one coat of primer to cleaned surface of all external railings (colour to be specified by Project Architect).	119	ln. ft		
<b>3</b>	<b>Flooring</b>				
3.1	Apply 2# coats of 'Weather Barrier', emulsion paint on prepared surface of Front Entry Hallway floor (colour to be specified by Project Architect).	1,220	sq ft		
3.2	Apply 2# coats of 'Weather Barrier', emulsion paint on prepared surface of Arrivals Gallery floor (colour to be specified by Project Architect).	218	sq ft		
<b>4</b>	<b>Ceilings</b>				
4.1	Clean dust and mildew from all external timber rafters and roof boards.	1	sum.		
<b>5</b>	<b>General</b>				
5.1	Clean site and make good.	1	sum.		
<b>6</b>	<b>Miscellaneous</b>				
6.1	Scaffolding	1	sum.		
6-2	Transportation:	1	sum.		
<b>7</b>	<b>Total:</b>				<b>EC\$</b>