



**MINISTRY OF COMMUNICATIONS, WORKS & LABOUR**

**P O BOX 344, BRADES, MONTSERRAT, W I**

◆ Tel: (664) 491-2521/2522 ◆ Fax: (664) 491-6659 ◆ E-mail: [mcw@gov.ms](mailto:mcw@gov.ms)

---

October 27<sup>th</sup>, 2017

Dear Sir/Madam,

**ADDENDUM No. 1 – Clarification and update to Bill of Quantities**

**Re: Tender for Construction of Reinforced Concrete Road in Judy Piece – Section 1 - 3**

Please note below the addendum to the Bill of Quantities for the Tender for the Construction of Reinforced Concrete Road in Judy Piece Section 1-3 under the Road Maintenance project, issued on the October 12<sup>th</sup> 2017.

Original

3.01 - Supply and place 200mm (6") thick in-situ concrete to comply with 3000 psi at 28-days for construction of reinforced concrete slab. Freshly placed concrete shall be poked vibrated and shall be broomed finish.

Update

3.01 - Supply and place between **150mm (6") to 200mm (8")** thick in-situ concrete to comply with 3000 psi at 28-days for construction of reinforced concrete slab. Freshly placed concrete shall be poked vibrated and shall be broomed finish.

All queries and clarification relating to this tender should be sent to Mr. Junior Bruce, Director, PWD at [brucej@gov.ms](mailto:brucej@gov.ms) or Mr. Rawlson Patterson, Civil Engineer at [pattersonr@gov.ms](mailto:pattersonr@gov.ms).

Best Regards

.....  
Beverly Mendes

**Chairperson**

**Departmental Tender Committee**

**Ministry of Communications, Works & Labour**

BEM/gf