

Revised Scope of Works

This is a total cost contract inclusive of materials, labour, transportation, profits and overheads.

SCOPE of WORKS – Deconstruction and Disposal of Debris of Blocks L and M Montserrat Secondary School, Salem.

The following items are considered to be **WITHIN** the scope of the proposed Deconstruction and Disposal of Debris of Blocks L and M, Montserrat Secondary School, Salem.

Deconstruction

- Secure work site
- Deconstruction of Blocks L and M (including all foundations, walk-ways, etc.).
- Dispose all deconstructed debris from site, in accordance with instructions from the Ministry of Education and /or their project supervision representatives.
- Cleaning, leveling and tidying up of site.

Deconstruct as per existing buildings:

Blocks L and M, MSS Salem.

- Deconstruction:
 - ROOF
 - WALLS
 - FLOOR
 - FOUNDATION: Remove All Concrete and reinforcement. Fill, level and make safe all trenches.
- Make good and tidy up grounds:
 - MAKE GOOD GROUNDS: Fill, level and make safe all trenches.
 - CLEAN UP: Remove **All Construction /non-Construction** debris from site and dispose of in accordance with instructions from the Ministry of Education and /or their project supervision representatives.